Item No.: 7b\_supp
Date of Meeting: May 6, 2014

# International Arrivals Facility Project Delivery



# Big Picture Issues

- Budget/Cost
  - Budget Confidence / Certainty
  - Cost Commitments / Risk
  - Cost Control
- Fast Track
  - i.e. overlap of design and construction phases
- Maintaining design quality using Design Build

## Timeline / Process Questions

- Budget / Cost
  - What is the progression of committed costs?
  - What is the point of no return? Off ramps?
  - When/how is the budget established?
  - How are costs controlled?
  - When is the actual cost known?
- When is the Design Builder engaged
  - What is the contractual commitment?
  - When is the point of no return?
- How far along will the design be when construction starts?
- What are the commission authorization/decision points?

# **Project Delivery Methods**

- Fundamentals of successful project management are common to all delivery methodologies.
- Challenges posed by the traditional Design-Bid-Build method have led to interest in alternative delivery methods.
- The industry shift to these alternatives, including Design Build, is because they have proven to be better solutions for Owners for many types of projects.

# Design Build

Design Build ("DB") is the consolidation of design and construction under one contract.

Benefits of DB include:

- Single point of accountability
- Ability to compress schedule
- Integrated holistic process
- Shift of risks from Owner to Design Builder starts at beginning of design

# Lump Sum DB vs. Progressive DB

## Lump Sum Design-Build (LSDB)

 Contract is awarded on fixed price based on Owner furnished partial design.

## <u> Progressive Design Build (PDB)</u>


 Design Builder and Owner collaborate to design to Owner's validated budget. Guaranteed Maximum Price (GMP) is established later in design process.



## **Process Overview**


**Develop Translate Procure Proceed with** Initiate Conceptual **Quantify Facility Performance Complete Subcontracts Program Design Based on** Stages of Performance Requirements & Start Construction **Development Project** Design Requirements into Project Construction **Process Definition Development Definition** 


# International Arrivals Facility (IAF) Program General Program Timeline



**Stakeholder Involvement** 

#### International Arrivals Facility (IAF) Program Procurement and Cost Control





5/6/2014 10

## Qualifications Based Selection

- Best team is best route to successful project
  - "Qualified" team brings to bear the skills, experience, resources and capabilities needed to be successful
  - Team alignment with Port's goals harnesses those capabilities for the benefit of the project
  - Port partners with Design Builder to achieve program goals
- A talented and motivated team working in alignment with and on behalf of the Port is the formula for optimal outcome

# Design Builder Validation Phase

#### Design Builder:


- Reviews Program Definition Documentation
- Conducts exhaustive site investigations
- Produces estimate and schedule based on Program Definition and all other information gathered
- Researches codes and regulatory requirements
- Takes ownership of Program Definition, Budget and Schedule

## Guaranteed Maximum Price (GMP)

- GMP caps cost exposure, shifts risk to Design Builder
- Reached by mutual agreement open book" process
- Includes sub pricing, validated estimates, business terms, GCs, allowances and contingencies
- Timing varies as early as possible once scope has been defined.
- Construction schedule also a major factor in timing of the GMP
- Savings revert to Port less any performance incentives
- Design Builder responsible for GMP overage
- Port may terminate contract if GMP agreement not reached



## **GMP Cost Distribution**



5/6/2014 1

# Design Control

- Program Definition
- Structured review process
  - Design Progress Reviews
  - Construction Packages
  - Alternates and Substitutions
  - Mock-ups
- Focus on design intent and compliance with technical criteria
- Multiple specialized reviews
  - Building Information Modeling / Focus Groups /
     IAF Decision Committee
- Design is monitored for adherence to comprehensive Program Definition documents



# **Quality Control**

- The GMP will include mutually agreed upon assumptions for quality.
  - Design Quality Control Plan
  - Construction Control Plan
  - Work Plans
  - Port verification of adherence to Plans
- Quality Approach can be scored in the RFP
- Design Builder's Quality Manager will report outside of the project organization and will partner with the Port to assure a quality product

## Recap

- Progressive Design Build is the right delivery method for the IAF to achieve budget, schedule and quality goals
  - Early budget validation will provide a high degree of confidence prior to major cost commitments
  - Schedule compression can be accomplished with less risk to the Owner
  - Quality results are achieved based on mutually agreed upon performance standards