Item No.: 4f_supp


Date of Meeting: September 22, 2015

Concourse C - New Power Center

Commission Briefing September 22, 2015



Project Location




New Power Center will serve power needs at North end of Concourse C.

Three Issues on Concourse C

- 1. Existing Concourse C Power Center is close to maximum capacity
 - no power for new projects/equipment.
- 2. Fire zones in Concourse C are compromised
 - unsafe conditions for emergency response.
- 3. Obsolete distribution equipment at existing electrical room
 - Risk of failure, no replacement parts.

Existing Concourse C Power Center

- 1. Two separate power feeds for redundancy and reliability.
- 2. Each Bus can be loaded to 1000A Maximum.
- Projected loads over next three years put us over the maximum allowed load.
 - No new electrified equipment.
 - Impacts operations, airline tenants, ADR.



Existing Power Center on Concourse C will be overloaded in 3 years.

Fire Zones

- 1. Electrical Power Distribution Fire Zones.
 - All equipment in a fire zone to be powered by a power source within the same zone.
 - Some Concourse C loads are currently fed from the C1 Power Center, located in a different fire zone.
- 2. Project will re-feed loads from the new Power Center, re-establishing fire zone integrity.

Electrical Distribution Issues

- 1. Distribution equipment at end of Concourse C does not have spare capacity.
 - Branch circuit panels have few or no spare breakers.
 - Tenant panels are obsolete configuration with outdated meters.
 - Power for new Tenant spaces is minimally available, installation is expensive.
- 2. Project will replace old panels and install new distribution with ample capacity.

Outdated Distribution Panel



Replacement breakers not available – failure will result in extended outage

Meters not networked – manual meter readings required

Modules no longer manufactured – cannot add new tenant services

Obsolete equipment poses risk of unplanned, extended outages.

Risk of Status Quo

- 1. Existing Concourse C Power Center projected to be at maximum capacity within the next 3 years.
- 2. New projects will not be able to install electrical equipment.
 - Airline tenant projects, ADR, operations could be impacted.
- 3. Risk of unplanned and extended outages.
 - Existing equipment is reaching end of life, may fail with no available spare parts.

Opportunities

Combining this project with the eGSE Phase 2 project for the construction phase provides opportunity to:

- Manage one Major Contract
- Accelerate schedules for both projects.
- Reduce design and construction costs.
- Consistency of design, supply and installation of major equipment.

Accelerated schedule and reduced cost by combining with eGSE Phase 2.

Schedule

 Start Design 	4 th Quarter 2015
 Complete Design 	1 st Quarter 2016
 Commission Authorization 	1 st Quarter 2016
for Construction	
 Advertise for Construction 	1 st Quarter 2016
 Substantial Completion 	4 th Quarter 2017

Project schedule will be complete in 4th Quarter 2017.

Project Budget

Estimated project Cost prior to design:

```
• Design Cost (18.1%) $1,900,000
```

Questions?