

This document is a text-only reovery of the original PDF file. Any graphics that were in the original PDF are not included here. If you need the original document, please contact the Commission Clerk at the Port of Seattle.

Item No. 8f\_supp  
Meeting Date: October 24, 2023  
Baggage Claim 15 & 16 Replacement Project  
Construction Authorization (C801127)

October 24, 2023

Project Purpose / Scope

Purpose:

- Replace the oldest baggage claim devices 15 & 16.
- Increase maintainability and reliability with new equipment.
- Increase tug lane width in the bag well to improve safety during drop off.
- Creates additional tenant lease space.

Scope:

- Design and construct replacement of baggage claims 15 & 16 flat plate devices with updated slope plate devices.
- Build 1000sf of flex space in the bag claim area for future tenants.

Existing Claims Devices

- Existing claims 15 & 16 have a total of 492 linear feet of claim frontage.
- Flat plate devices do not allow for double stacked baggage.

New Claim Devices

- Slope plate design has 321 linear feet of claim frontage
- Slope plate width is 5 feet which allows for double stacked bag storage, increasing overall capacity

Preliminary Construction Schedule

Event Date

Advertise for Construction Bids Q1 2024

Procure Long Lead Items Q2 2024

Construction Begin (Notice to Proceed) Q4 2024

Substantial Completion (Both Claims Complete) Q3 2025

Project Budget

Phase Cost

Design \$3,667,000

Construction \$10,658,000

Total \$14,325,000

Project Benefits

- ? Replaces the oldest baggage claim devices
- ? Reduces maintainability and reliability issues
- ? Increases tug traffic safety in the bag well
- ? Creates more tenant lease space

Thank

You!

Operated by the

Port of Seattle

FlySEA.org